SolveLog

A Practice Journal, Spaced-Revision System and Public Portfolio for Competitive Programmers

Project Report: Software Requirements Specification (IEEE 830 format)
with UML Diagrams, Estimation, Test Cases, Testing Techniques and Results

Submitted by: Manthan Vats

Live application: https://solvelog.vercel.app

Source code: https://github.com/Manthan-Vats/competitive-programming-journal

Diagrams and report repository: https://github.com/Manthan-Vats/SolveLog-SE-Project

Date: November 2026

Table of Contents

1. Introduction
2. Overall Description
3. Specific Requirements
4. System Design and UML Diagrams
5. Project Estimation
6. Testing: Techniques, Test Cases and Results
7. Implementation and Screenshots
8. Conclusion and Future Scope
9. References

Appendix A: Glossary · Appendix B: Requirements Traceability Matrix

1. Introduction

1.1 Purpose

This document is the Software Requirements Specification (SRS) and project report for **SolveLog**. It defines what the system must do (functional requirements), how well it must do it (non-functional requirements), and how it was designed, estimated, built and tested. The intended readers are the project evaluator, future maintainers of the code base, and anyone deploying their own instance.

1.2 Problem Statement

Competitive programmers solve problems on many judges (Codeforces, LeetCode, AtCoder, CodeChef …), but their work ends up scattered. Three things are missing:

1. **Retention.** A problem solved once is usually forgotten within weeks, because nothing schedules a revisit at the right time.
2. **Insight.** Judges show a verdict, not the *pattern* that was used (two pointers, DP on trees …), so learners cannot see which techniques they rely on or avoid.
3. **Proof of work.** No single, curated page shows a recruiter or mentor what someone has actually solved and how.

1.3 Scope

SolveLog is a multi-tenant web application plus a companion browser extension that:

- captures problems and accepted solutions from judge sites (one click, or automatic import)
- stores them in a private, per-user journal with timing data
- tags each solution with algorithms, data structures and techniques using AI (Google Gemini, with a bring-your-own-key model)
- schedules revision with the **FSRS** spaced-repetition algorithm
- shows analytics (streaks, heatmap, pattern coverage, weakest area)
- publishes a curated public portfolio at `/u/<handle>` with shareable achievement cards

Out of scope: running or judging code (no online judge), contests, and social features such as following or comments.

1.4 Definitions, Acronyms and Abbreviations

Term	Meaning
Judge	An online platform that hosts problems and verifies submissions (e.g., Codeforces)
FSRS	Free Spaced Repetition Scheduler, a modern memory model that computes the next review date
RLS	Row Level Security, Postgres policies that restrict which rows a user can read or write

Term	Meaning
BYOK	Bring Your Own Key: each user supplies their own Gemini API key
Operator	The single administrator who approves access requests
Companion	The SolveLog browser extension (Chrome / Firefox, Manifest V3)
SRS	Software Requirements Specification
SSR	Server-Side Rendering

1.5 References

See Section 9.

1.6 Overview of the Document

Section 2 describes the product at a high level. Section 3 lists the detailed requirements. Section 4 presents the design through 16 UML and structured-analysis diagrams. Section 5 estimates size, effort and cost. Section 6 covers testing techniques, test cases and results. Sections 7–8 show the implementation and conclude.

2. Overall Description

2.1 Product Perspective

SolveLog is a new, self-contained product. It follows a three-tier, cloud-hosted architecture:

- **Presentation tier:** Next.js (React 19) pages, server-rendered and hydrated in the browser, plus the Companion extension.
- **Application tier:** Next.js route handlers (`/api/**`) on Vercel's Node.js runtime.
- **Data tier:** Supabase (PostgreSQL 15 + Auth), where Row Level Security is the security boundary.

External systems: Google Gemini (with Groq as a fallback provider) for AI analysis, and the public APIs and pages of Codeforces and LeetCode for imports and handle verification.

2.2 Product Functions (summary)

1. Invite-only access: request access → operator approves → invite email → set password → sign in
2. Problem journal: create, edit, delete and search problems; metadata auto-filled from the URL
3. Solutions: multiple per problem, with language, code (Monaco editor), verdict and runtime
4. Timing: start/stop timer per attempt (web or extension widget)
5. AI analysis: tags each solution; AI hints, code critique and "pattern card" during revision (cached)
6. Revision: FSRS-scheduled queue; grade Again / Hard / Good / Easy; suspend a card
7. Analytics: streak, activity heatmap, difficulty and platform split, pattern coverage
8. Public portfolio: per-problem publish toggles, public profile, achievement card and rating badges
9. Companion extension: one-click capture, floating timer, bulk import of past submissions
10. Settings: profile, verified judge handles, AI key, extension tokens, theme, account deletion

2.3 User Classes and Characteristics

User class	Description	Technical skill
Visitor	Not signed in; views public portfolios and can request access	Any
User (member)	Invited programmer who keeps a private journal	Comfortable with judges and browsers
Operator	Runs the instance; approves or rejects access requests	High

2.4 Operating Environment

- **Client:** any modern browser (Chrome, Edge, Firefox, Safari), desktop or mobile; extension on Chromium browsers and Firefox
- **Server:** Vercel (Node.js 24 runtime, serverless functions)
- **Database:** Supabase-hosted PostgreSQL with Supabase Auth

2.5 Design and Implementation Constraints

- The browser holds a **public** Supabase anon key, so every table must be protected by RLS.
- Service-role key is server-only and never exposed with a `NEXT_PUBLIC_` prefix.
- Judge solution code is behind the user's own judge session; the server must **never** store judge credentials. Imports therefore run inside the user's browser via the extension.
- Free-tier hosting limits (function duration, database size, AI quota) shape the design: AI work runs after the response (`after()`), and AI results are cached.

2.6 Assumptions and Dependencies

- Users have an account on at least one supported judge.
- Gemini API keys are available free of charge from Google AI Studio.
- Judge sites keep their public page structure and APIs reasonably stable; parsers are covered by fixture tests so breakage is detected.

3. Specific Requirements

3.1 External Interface Requirements

User interfaces. Responsive web UI with a paper-notebook theme (light by default, optional dark "night file" theme). Main screens: landing, login, dashboard, problems list, problem detail, add problem, analytics, revision, settings, invites (operator), public portfolio.

Hardware interfaces. None beyond a standard PC or phone.

Software interfaces.

Interface	Purpose	Protocol
Supabase Auth	Sign-in, invites, password reset	HTTPS / JWT cookies
Supabase PostgREST	All data access under RLS	HTTPS / JSON
Google Gemini API	Solution analysis, hints, critique	HTTPS / JSON
Groq API	Fallback AI provider	HTTPS / JSON
Codeforces API	Metadata, user stats, handle verification	HTTPS / JSON
LeetCode GraphQL	Metadata, stats, imports	HTTPS / GraphQL

Communication interfaces. HTTPS only. The extension authenticates with a revocable bearer token (only its SHA-256 hash is stored server-side).

3.2 Functional Requirements

ID	Requirement	Priority
FR-1	A visitor shall be able to submit an access request with a valid email address.	High
FR-2	The operator shall be able to approve (send invite) or reject a pending request.	High
FR-3	An invited user shall set a password and sign in with email and password; a forgotten password can be reset by email.	High
FR-4	A signed-in user shall create, edit, delete and list their own problems.	High
FR-5	When a problem URL is entered, the system shall fetch title, difficulty and tags from the judge where possible.	Medium
FR-6	A user shall attach one or more solutions (language, code ≤ 100,000 chars, verdict) to a problem.	High
FR-7	A user shall record timed attempts (start, stop, manual entry).	Medium
FR-8	If the user has stored a Gemini key, the system shall analyse each new or changed solution and store algorithms, data structures, techniques and confidence.	Medium
FR-9	The system shall keep a revision card per problem and compute the next due date with FSRS after each grade (Again / Hard / Good / Easy).	High

ID	Requirement	Priority
FR-10	A user shall be able to suspend and resume a problem's revision card.	Low
FR-11	During revision, a user may request an AI hint, a critique of their code, or a pattern card; results are cached per problem and code hash.	Low
FR-12	The system shall show analytics: streak, heatmap, counts by difficulty and platform, and pattern coverage.	Medium
FR-13	A user shall choose which problems and which solution code are public; everything is private by default.	High
FR-14	Anyone shall be able to view a user's public portfolio at `/u/<handle>` and download an achievement card image.	Medium
FR-15	A user shall verify ownership of a judge handle with a one-time token and display verified stats.	Low
FR-16	The Companion extension shall capture the current judge problem and accepted solution with one click.	High
FR-17	The extension shall import past accepted submissions in bulk without the server ever seeing judge credentials.	Medium
FR-18	A user shall be able to create, label and revoke extension tokens.	High
FR-19	A user shall be able to store, replace and delete their AI key; it is encrypted at rest.	Medium
FR-20	A user shall be able to permanently delete their account and all owned data.	Medium

3.3 Non-Functional Requirements

ID	Category	Requirement
NFR-1	Security	Every table has RLS; a user can read or write only their own rows, plus rows explicitly published by their owner.
NFR-2	Security	Secrets (service-role key, AI-key encryption key) never reach the client. AI keys are encrypted with AES-256-GCM.
NFR-3	Security	Extension tokens are stored only as SHA-256 hashes and can be revoked.
NFR-4	Security	Write and AI endpoints are rate-limited (Postgres-backed fixed window); the limiter fails open.
NFR-5	Performance	Landing page time-to-first-byte under 1 s; Lighthouse performance score of 90 or more.
NFR-6	Performance	Saving a solution must not wait on AI; AI runs after the HTTP response.
NFR-7	Reliability	An AI outage must never fail a create or update; the solution is marked `ai_status = failed` instead.
NFR-8	Usability	Responsive down to 360 px width; keyboard-navigable forms; light and dark themes.
NFR-9	Maintainability	TypeScript strict mode; shared enums in one module; parsers covered by fixture tests.

ID	Category	Requirement
NFR-10	Portability	Runs on any Next.js host plus any Supabase project; schema is fully reproducible from 17 SQL migrations.
NFR-11	Privacy	Data is private by default; publishing is an explicit per-item action.


3.4 Database Requirements

The persistent data model has 13 relations (see Section 4.8): `problems`, `solutions`, `ai_analyses`, `timing_sessions`, `profile`, `review_cards`, `extension_tokens`, `access_requests`, `platform_verifications`, `user_ai_keys`, `ai_assists`, `rate_limits`, and Supabase's `auth.users`. All user-owned tables carry a `user_id` foreign key to `auth.users` with `ON DELETE CASCADE`, so deleting an account removes its data.

4. System Design and UML Diagrams

All diagrams are kept intentionally compact. The Mermaid source for every diagram is in the `diagrams/` folder of the report repository and can be regenerated in any Mermaid renderer.

4.1 Use Case Diagram




Three human actors (Visitor, User, Operator) and two system actors (Companion Extension, Gemini AI). *Log problem* includes *Sign in*; *Add solution* includes *Analyze solution*; *Get AI hint* is an optional extension of *Revise problems*.

Use case specification: UC-5 Add Solution

Field	Description
Actor	User
Pre-condition	User is signed in and owns the problem
Main flow	1. User opens a problem. 2. Pastes code and selects language. 3. Clicks Save. 4. System validates and stores the solution. 5. System shows it with AI status "pending". 6. If a key is set, the system analyses the code and shows the tags.


Field	Description
Alternate flow	4a. Code empty or over 100,000 chars → error shown, nothing saved. 6a. No AI key → status "none", no tags. 6b. AI fails → status "failed"; the solution is still saved.
Post-condition	Solution stored; analysis stored if available

4.2 Class Diagram




Operator specialises User. A Problem is composed of Solutions, TimingSessions and at most one ReviewCard; a Solution owns at most one AIAnalysis.

4.3 Object Diagram




A snapshot after a user logs "Two Sum", saves an accepted C++ solution that the AI tags as hashing, and has reviewed the problem three times.


4.4 Sequence Diagrams




The response (201) returns **before** the AI call, which runs in `after()`; this implements NFR-6.



4.5 Activity Diagram




4.6 State Machine Diagram





FSRS card states: New → Learning → Review, with Relearning after a lapse.

4.7 Communication Diagram





4.8 Entity-Relationship Diagrams







4.9 Package, Component and Deployment Diagrams



«package» ui
Pages
Components
«package» extension
Background
Content Scripts
«access»
«access»
«package» api
Route Handlers
«import»
«import»
«package» lib
ai
fsrs
import
supabase
«access»
«package» database
Migrations + RLS






4.10 Data Flow Diagrams





4.11 Control Flow Graph

The CFG for `cfRatingToDifficulty()` (`lib/difficulty.ts`) is used for basis-path testing in Section 6.4.


1
F
3
F
5
T
T
F
T
7
T
F
2
4
6
8
9
10

5. Project Estimation

5.1 Size Metrics (measured)

Lines of code were counted from the repository (TypeScript/TSX source, blank lines and comments included, generated files and dependencies excluded).

Module	Files	LOC
`app/` (pages + API routes)	65	8,486
`components/` (UI)	55	7,686
`lib/` (domain logic, AI, FSRS, import)	39	3,025
`extension/` (entrypoints + lib)	24	3,153
`types/`	1	136
Application total	**184**	**22,486 (≈ 22.5 KLOC)**
`supabase/migrations/` (SQL)	17	1,029
Tests (web + extension)	20	1,536

5.2 Function Point Analysis

Unadjusted Function Points (UFP)

Component	Simple	Average	Complex	UFP
External Inputs (EI): add/edit/delete problem, add/edit solution, grade, suspend, profile, AI key, access request, approve/reject, capture, import, timer, publish, verify handle	5 × 3	8 × 4	3 × 6	65
External Outputs (EO): analytics, AI analysis, portfolio, achievement card, badge, revision queue	—	4 × 5	2 × 7	34
External Inquiries (EQ): problem search, problem detail, metadata lookup, review queue, token check, access-request list	2 × 3	4 × 4	—	22
Internal Logical Files (ILF): the 12 application tables	8 × 7	4 × 10	—	96
External Interface Files (EIF): Supabase Auth users, Gemini, Codeforces API, LeetCode GraphQL	2 × 5	2 × 7	—	24
Total UFP				**241**

Value Adjustment Factor. The 14 general system characteristics were rated 0–5: data communications 5, distributed processing 4, performance 3, heavily-used configuration 2, transaction rate 2, online data entry 5, end-user efficiency 4, online update 4, complex processing 3, reusability 3, installation ease 2, operational ease 3, multiple sites 3, facilitate change 4. **Σ = 47**.

VAF = 0.65 + 0.01 × 47 = **1.12**

FP = 241 × 1.12 = 269.9 ≈ 270 FP

Using a typical JavaScript/TypeScript gearing factor of ~47 LOC/FP, this predicts ≈ 12.7 KLOC. The measured 22.5 KLOC is higher because about a third of the code is presentation (custom animated paper-themed UI components), which function points do not count.

5.3 COCOMO (Basic), Organic Mode

KLOC = 22.5; organic constants a = 2.4, b = 1.05, c = 2.5, d = 0.38.

Quantity	Formula	Result
Effort	E = 2.4 × (22.5)^1.05	**63.1 person-months**
Development time	D = 2.5 × (63.1)^0.38	**12.1 months**
Average staff	P = E / D	**5.2 persons**
Productivity	KLOC / E	0.36 KLOC/PM (356 LOC/PM)

5.4 COCOMO (Intermediate)

Nominal effort (organic, a = 3.2): E_{nom} = 3.2 × (22.5)^1.05 = 84.1 PM.

Cost driver	Rating	Multiplier
RELY: required reliability (security-critical data isolation)	High	1.15
DATA: database size	High	1.08
CPLX: product complexity (AI, scheduling, parsers)	High	1.15
MODP: modern programming practices	High	0.91
TOOL: use of software tools (frameworks, BaaS, CI)	Very High	0.83
All others	Nominal	1.00
EAF		**1.079**

E = 84.1 × 1.079 ≈ 90.7 person-months.

5.5 Cost Estimate

Using an indicative fresher developer cost of ₹40,000 per person-month (Basic COCOMO): 63.1 PM × ₹40,000 ≈ **₹25.2 lakh**. Running cost on the current free tiers (Vercel Hobby, Supabase Free, Gemini free tier with BYOK) is **₹0 per month**.

5.6 Discussion: Estimated vs Actual

The project was built by **one developer**, far below the 5-person, 12-month team that COCOMO predicts. The gap is expected and has known causes. COCOMO was calibrated on 1970s–80s projects where every subsystem was written from scratch. Here, whole subsystems come off the shelf: authentication, database and REST API (Supabase), hosting and CI/CD (Vercel), UI primitives, the FSRS algorithm (ts-fsrs) and the code editor (Monaco). AI-assisted development tools also raise individual productivity. The estimates are therefore best read as the effort to build an equivalent system *without* those platforms.

5.7 Schedule (Phases)

Phase	Work
1. Requirements & planning	Problem study, feature list, data model, security model
2. Core backend	Schema and migrations, RLS, auth, problems/solutions APIs
3. Extension	Judge parsers, capture, timer widget, background import
4. AI layer	Provider abstraction (Gemini + Groq), async analysis, BYOK encryption, caching
5. Revision & analytics	FSRS integration, queue, grading, dashboards
6. UI/UX	Paper-theme redesign, accessibility and contrast pass, dark mode
7. Testing & hardening	Unit/fixture tests, security audit fixes, rate limiting
8. Launch	Deploy to Vercel, rebrand to SolveLog, public repository

6. Testing

6.1 Testing Strategy and Techniques Used

Level / technique	What was done	Tooling
Unit testing	Pure modules (FSRS wrapper, difficulty mapping, pattern normalisation, AES-GCM secret box, import batching, judge parsers) tested in isolation	TypeScript test scripts run with `tsx`
Black-box: Equivalence Partitioning	Inputs split into valid and invalid classes (e.g., rating ≤ 0 / missing vs each difficulty band; valid vs invalid email; valid vs revoked token)	Unit tests + HTTP tests
Black-box: Boundary Value Analysis	Values on and around each boundary: 0, 1299/1300, 1899/1900, 2399/2400	Unit tests
White-box: Basis Path testing	CFG drawn, cyclomatic complexity computed (V(G) = 5), one test per independent path	Section 6.4
Fixture-based (regression) testing	Saved real HTML/JSON pages from Codeforces, LeetCode, AtCoder and CodeChef are re-parsed on every run to catch parser regressions	Extension test suite
Integration testing	Route handler + Supabase + RLS exercised end to end during development	Manual + browser
System / API testing	HTTP requests against the deployed production build	`curl`
Security testing	Unauthenticated and invalid-token access to protected endpoints; method restrictions; input validation	`curl`
Static analysis	Type checking and linting of the whole code base	`tsc --noEmit`, ESLint
Performance testing	Time-to-first-byte measurement; Lighthouse audit	`curl`, Lighthouse
User acceptance testing	Developer and invited users walked through core flows on the live app	Manual

6.2 Automated Unit Test Results

All suites were executed on **1 November 2026** (Node.js 22.17).

#	Suite	Module under test	Assertions	Result
1	`difficulty.test.ts`	Difficulty bands, enum allowlists	29	PASS
2	`fsrs.test.ts`	FSRS card creation, grading, serialisation	20	PASS
3	`import-batch.test.ts`	Bulk import batching and dedup	20	PASS
4	`import-judges.test.ts`	Judge API response parsing	24	PASS
5	`solution-provenance.test.ts`	Verdict / submission provenance	21	PASS

#	Suite	Module under test	Assertions	Result
6	`verify.test.ts`	Handle-verification logic	18	PASS
7	`patterns.test.ts`	Pattern taxonomy	17	PASS
8	`html-text.test.ts`	HTML → text sanitising	14	PASS
9	`ai-key-validate.test.ts`	AI key format validation	10	PASS
10	`ai-schema.test.ts`	AI response schema validation	10	PASS
11	`secret-box.test.ts`	AES-256-GCM encrypt/decrypt, tamper detection	8	PASS
12	`ai-registry.test.ts`	Provider registry and fallback	6	PASS
13	`normalize-patterns.test.ts`	AI tag normalisation	6	PASS
14	`ext/leetcode.test.ts`	LeetCode page parser	16	PASS
15	`ext/deep-leetcode.test.ts`	LeetCode deep import	42	PASS
16	`ext/deep-codeforces.test.ts`	Codeforces deep import	41	PASS
17	`ext/atcoder_codechef.test.ts`	AtCoder / CodeChef parsers	17	PASS
18	`ext/cf-statement.test.ts`	Codeforces statement extraction	13	PASS
19	`ext/mathjax.test.ts`	MathJax → text conversion	7	PASS
	Total	**19 suites**	**339**	**339 / 339 PASS (100%)**

6.3 Black-Box Test Cases: `cfRatingToDifficulty(rating)`

Equivalence classes: **E1** missing or ≤ 0 → unknown; **E2** 1–1299 → easy; **E3** 1300–1899 → medium; **E4** 1900–2399 → hard; **E5** ≥ 2400 → expert. Boundary values were taken on each edge.

TC ID	Technique	Input	Expected	Actual	Status
BB-01	EP (E1)	`undefined`	unknown	unknown	PASS
BB-02	EP (E1)	`null`	unknown	unknown	PASS
BB-03	BVA (E1 edge)	0	unknown	unknown	PASS
BB-04	EP (E2)	800	easy	easy	PASS
BB-05	BVA (E2 upper)	1299	easy	easy	PASS
BB-06	BVA (E3 lower)	1300	medium	medium	PASS
BB-07	BVA (E3 upper)	1899	medium	medium	PASS
BB-08	BVA (E4 lower)	1900	hard	hard	PASS
BB-09	BVA (E4 upper)	2399	hard	hard	PASS
BB-10	BVA (E5 lower)	2400	expert	expert	PASS

6.4 White-Box Test Cases: Basis Path Testing

From the CFG in Section 4.11: N = 10 nodes, E = 13 edges.

Cyclomatic complexity V(G) = E − N + 2 = 13 − 10 + 2 = 5 (check: 4 predicate nodes + 1 = 5). So there are 5 independent paths, and 5 test cases are enough for full path coverage.

TC ID	Independent path	Input	Expected	Actual	Status
WB-01	1 → 2 → 10	0	unknown	unknown	PASS
WB-02	1 → 3 → 4 → 10	800	easy	easy	PASS
WB-03	1 → 3 → 5 → 6 → 10	1300	medium	medium	PASS
WB-04	1 → 3 → 5 → 7 → 8 → 10	1900	hard	hard	PASS
WB-05	1 → 3 → 5 → 7 → 9 → 10	2400	expert	expert	PASS

Result: **100% statement, branch and basis-path coverage** for this function.

6.5 Other Functional Unit Test Cases (selected)

TC ID	Module	Test	Expected	Status
UT-01	FSRS	New card has state New (0) and 0 reps	state = 0, reps = 0	PASS
UT-02	FSRS	Preview next-due dates for all four grades	due(Again) ≤ due(Good) ≤ due(Easy)	PASS
UT-03	FSRS	Stored card round-trips through JSON and is graded again	reps = 2, dates stored as ISO strings	PASS
UT-03b	FSRS	Grade value validation	1–4 accepted; 0, 5 and "good" (string) rejected by `isGrade`	PASS
UT-04	Secret box	Encrypt then decrypt	Original plaintext	PASS
UT-05	Secret box	Tampered ciphertext	Decryption throws (auth-tag check)	PASS
UT-06	Secret box	Wrong master key	Decryption fails	PASS
UT-07	Difficulty	LeetCode "Medium"	medium	PASS
UT-08	Difficulty	Language "brainfuck"	rejected by allowlist	PASS
UT-09	AI schema	Response schema adapted per provider	Gemini drops unsupported `$schema` / `additionalProperties`; Groq keeps strict `additionalProperties:false`; enums preserved	PASS

TC ID	Module	Test	Expected	Status
UT-10	Import batch	Same problem twice in one batch	One problem row, both solutions kept	PASS
UT-11	Import batch	Invalid problem in batch	Counted as invalid; its solutions dropped	PASS

6.6 System and Security Test Cases (production deployment)

Executed on **1 November 2026** against `https://solvelog.vercel.app` with `curl`, signed out.

TC ID	Test	Request	Expected	Actual	Status
ST-01	Landing page loads	`GET /`	200	200	PASS
ST-02	Login page loads	`GET /login`	200	200	PASS
ST-03	Admin is protected	`GET /admin` (no session)	Redirect to `/login`	307 → `/login`	PASS
ST-04	Unknown portfolio	`GET /u/this-handle-does-not-exist-xyz`	404	404	PASS
ST-05	Unknown route	`GET /nonexistent-page-zzz`	404	404	PASS
ST-06	Grade needs auth	`POST /api/review/grade`	401	401	PASS
ST-07	Review queue needs auth	`GET /api/review/queue`	401	401	PASS
ST-08	Create solution needs auth	`POST /api/solutions`	401	401	PASS
ST-09	Account delete needs auth	`DELETE /api/account`	401	401	PASS
ST-10	Extension needs token	`GET /api/ext/me` (no token)	401	401	PASS
ST-11	Invalid extension token rejected	`GET /api/ext/me` with `Bearer invalidtoken123`	401	401	PASS
ST-12	Email validation	`POST /api/access-requests {"email":"not-an-email"}`	400 "A valid email is required."	400, same message	PASS
ST-13	Method restriction	`GET /api/invites` (POST-only route)	405	405	PASS

TC ID	Test	Request	Expected	Actual	Status
ST-14	SEO files	`GET /robots.txt`, `GET /sitemap.xml`	200	200, 200	PASS
ST-15	Legal page	`GET /privacy`	200	200	PASS
ST-16	Public problem list (anonymous)	`GET /api/problems`	200 with published problems	Run 1: **500** · Re-test: 200, JSON list of published problems	FAIL → **PASS**
ST-17	Health check	`GET /api/heartbeat`	200 `{ok:true}`	Run 1: **500** · Re-test: 200 `{ok:true}`	FAIL → **PASS**
ST-18	Performance: TTFB	`GET /`	< 1 s	0.43 s (total 0.45 s)	PASS

Defect analysis for ST-16 and ST-17. Both endpoints query the database directly. During the first run (1 November 2026) the Supabase project host did not resolve in DNS, so every database call failed: the free-tier project had been automatically **paused** after a period of inactivity. The application code handled it correctly: it returned a clean 500 JSON error with no stack trace or secret leaked, and every non-database route kept working. This was an **environment** defect, not a code defect.

Corrective action and re-test: the project was restored from the Supabase dashboard and both cases were re-executed on **2 November 2026**. Both returned 200 with correct payloads, so the defect is **closed**. Preventive action: schedule a keep-alive call to `/api/heartbeat` (the endpoint already exists for this purpose) so the free tier never pauses again.

6.7 User Acceptance Test Cases (manual, during development)

TC ID	Scenario	Expected	Status
UAT-01	Request access → operator approves → invite email → set password → sign in	User lands on dashboard	PASS
UAT-02	Add problem from a Codeforces URL	Title, rating and tags auto-filled	PASS
UAT-03	Add solution with AI key set	Tags appear after a few seconds; status "done"	PASS
UAT-04	Add solution with no AI key	Saved; status "none"; no error	PASS
UAT-05	Capture an accepted LeetCode problem via extension	Problem and solution appear in journal	PASS
UAT-06	Extension floating timer start/stop	Timing session saved against problem	PASS
UAT-07	Revise: grade Good	Card leaves today's queue; next due in future	PASS

TC ID	Scenario	Expected	Status
UAT-08	Toggle problem public	Appears on `/u/<handle>` for a signed-out visitor	PASS
UAT-09	User A cannot see User B's private problems	Only A's rows in A's dashboard	PASS (after fix 509c074)
UAT-10	Revoke extension token	Extension requests return 401	PASS

6.8 Static Analysis Results

Check	Command	Result
Type checking	`tsc --noEmit`	**0 errors**: PASS
Linting	`eslint .`	140 errors, 349 warnings (non-blocking). Breakdown of errors: 98 `no-explicit-any`, 19 `react-hooks/set-state-in-effect`, 9 `ban-ts-comment`, 6 `react-hooks/purity`, 8 other. 14 of the 140 are in generated extension type files. None affect the production build. Logged as technical debt.
Production build	`next build`	Succeeds (deployed on Vercel)

6.9 Defects Found and Fixed During Development (selected)

ID	Defect	Severity	Root cause	Fix
D-01	Admin views showed other users' public problems	High	Relied on RLS alone; the public-read policy also matched other users' published rows	Explicit `.eq("user_id", user.id)` on all "my data" queries
D-02	Settings inputs lost focus after one character	Medium	Component defined inside render, so it was re-mounted every keystroke	Hoisted the component; removed SSR gating on mutable state
D-03	`ai_status` stuck on "pending"	Medium	Fire-and-forget self-fetch was dropped when the serverless function froze	AI runs in-process inside `after()`
D-04	Extension import failed for session-gated code	High	Background service worker lacked judge cookies	Import runs in a background judge tab via content script
D-05	Difficulty thresholds differed between routes	Low	Duplicated constants	Single source of truth in `lib/difficulty.ts` (covered by BB-01…BB-10)

6.10 Test Summary

Category	Executed	Passed	Failed	Pass rate
Automated unit assertions	339	339	0	100%

Category	Executed	Passed	Failed	Pass rate
Black-box cases (EP/BVA)	10	10	0	100%
White-box basis paths	5	5	0	100%
System / security (production)	18	18	0*	100%
User acceptance	10	10	0	100%

* ST-16 and ST-17 failed on the first run because the database was paused (an environment issue). They passed on re-test after the restore; see Section 6.6.

7. Implementation and Screenshots

Technology stack: Next.js 16 (App Router), React 19, TypeScript 5, Tailwind CSS 4, Supabase (PostgreSQL + Auth + RLS), ts-fsrs, Google Gemini (`@google/genai`) with Groq fallback, Monaco Editor, Recharts, GSAP, WXT (extension framework), Sentry (error monitoring), Vercel (hosting).

Screenshots were captured from the production deployment on 2 November 2026. A recorded walkthrough of the same flows (`demo/SolveLog_Demo.mp4`, 2 min 49 s) is in the project repository.




Figure 7.1: Landing page (signed out)




Figure 7.2: Invite-only sign-in




Figure 7.3: Dashboard with setup checklist, streak, revision counts and recent entries




Figure 7.4: Problem journal with search and filters




Figure 7.5: Problem detail: solution code and solve timer




Figure 7.6: Add problem: metadata auto-filled from a Codeforces URL (FR-5)




Figure 7.7: Analytics: activity heatmap, topic distribution, average solve time per topic




Figure 7.8: FSRS revision queue




Figure 7.9: Settings: profile, handles, AI key, extension tokens




Figure 7.10: Public portfolio at /u/<handle>

8. Conclusion and Future Scope

8.1 Conclusion

SolveLog meets its three goals. **Retention** comes from FSRS-scheduled revision. **Insight** comes from AI pattern tagging, coverage analytics and on-demand hints. **Proof of work** comes from a curated, private-by-default public portfolio. Security is enforced at the database layer with RLS, backed by explicit ownership checks, encrypted AI keys, hashed extension tokens and rate limiting. The automated suite of 339 assertions passes completely, and all 18 system tests against production pass. The two failures on the first run were traced to a paused database; they were fixed by restoring it and confirmed by re-testing.

8.2 Limitations

- Bulk import currently supports Codeforces and LeetCode deeply; other judges support capture only.
- AI features depend on the user providing a Gemini key.
- Free-tier hosting pauses the database after inactivity.

8.3 Future Scope

- Keep-alive scheduler (cron) to prevent free-tier database pauses
- Deep import for AtCoder and CodeChef
- Contest-mode practice timer and virtual contests
- Mentor view: share a read-only journal with a coach
- Clear the ESLint backlog (replace `any` types) and add end-to-end browser tests (Playwright)

9. References

1. IEEE Std 830-1998, *IEEE Recommended Practice for Software Requirements Specifications*.
2. R. S. Pressman, *Software Engineering: A Practitioner's Approach*, 8th ed., McGraw-Hill.
3. B. W. Boehm, *Software Engineering Economics*, Prentice Hall, 1981 (COCOMO).
4. A. J. Albrecht, "Measuring Application Development Productivity", IBM, 1979 (Function Points).
5. Object Management Group, *Unified Modeling Language Specification*, v2.5.1.
6. T. J. McCabe, "A Complexity Measure", *IEEE Transactions on Software Engineering*, 1976.
7. J. Ye et al., *FSRS: Free Spaced Repetition Scheduler*, open-spaced-repetition project.
8. Next.js Documentation: https://nextjs.org/docs
9. Supabase Documentation (Auth, Row Level Security): https://supabase.com/docs
10. Google Gemini API Documentation: https://ai.google.dev

Appendix A: Glossary

Accepted (AC): judge verdict meaning the solution passed all tests. **Lapse:** forgetting a reviewed card (graded Again). **Pattern:** a reusable problem-solving technique such as sliding window or binary search on answer. **Portfolio:** the public page at `/u/<handle>`.

Appendix B: Requirements Traceability Matrix

Requirement	Design artefact	Test case(s)
FR-1	Use case, DFD-0	ST-12, UAT-01
FR-2	Use case, class (Operator)	ST-13, UAT-01
FR-3	Use case, deployment	ST-02, ST-03, UAT-01
FR-4	Class, ER, activity	ST-08, UAT-02
FR-5	Activity	BB-01…BB-10, UT-07, UAT-02
FR-6	Sequence (add solution)	ST-08, UT-08, UAT-03
FR-7	Class (TimingSession)	UAT-06
FR-8	Sequence, DFD-1 (3.0)	UT-09, UAT-03, UAT-04
FR-9	State, communication	UT-01…UT-03, ST-06, UAT-07
FR-10	State (Suspended)	ST-07
FR-12	Component	UAT (dashboard)
FR-13	ER (`is_public`)	UAT-08, UAT-09
FR-14	Deployment	ST-04, UAT-08

Requirement	Design artefact	Test case(s)
FR-16	Sequence (capture)	ST-10, ST-11, UAT-05
FR-17	Package (extension)	UT-10, ext suites 14–19
FR-18	ER (extension_tokens)	ST-11, UAT-10
FR-19	Class, NFR-2	UT-04…UT-06
FR-20	ER (ON DELETE CASCADE)	ST-09
NFR-5	—	ST-18